

NATIONAL HEALTH SYSTEMS RESOURCE CENTRE



NOTICE INVITING QUOTATION

Ref: - NHSRC/A-01/04/08-PF2

Date:-10/04/2017

Name of the work: Providing and Fixing pre-coated galvanised iron Sheet with MS Frame at PSS and BSES Metering panel at NHSRC, NIHFV Campus, Munirka, New Delhi-110067.

1. Sealed item rate quotations are invited for above said work.
2. The bidder shall submit the EMD of Rs.2000.00 (Rs.Two Thousand Only) in form of Demand Draft/Bankers Cheque in favour of National Health Systems Resource Center along with quotation document. The quotation without EMD shall be rejected.
3. The work to be completed within 15 Days from the date of written instructions to carry out work.
4. The contractor should be registered with VAT & Service Tax. Proof of registrations should be attached with quotation.
5. Quotation submitted without the registration certificates shall be rejected.
6. All rates shall be quoted on the quotation form and shall include material, labour, transportation, all taxes & duties, supervision, tools, plants, wastage, sundries, scaffolding as required mobilization, demobilization, transportation etc. and nothing extra shall be payable on this account. However shall not include **the service tax**, which will be payable by department to contractor over and above quoted rates.
7. Necessary deductions shall be made on account of statutory deductions as applicable.
8. The work shall be done as per CPWD Specifications 2009.
9. The sealed quotation so as to reach this office on or before **17-04-2017** latest by 1500 hrs. The quotation will be opened at 1530 Hours on the same day.
10. The payment will be made after satisfactory completion of work and on actual measurement.
11. The quantities given in schedule may vary as per actual variation at site.
12. The contractor shall self attested all the quotation documents along with registration documents as required above.
13. The contractor whose bid is accepted will be required to furnish performance guarantee of 5% (Five Percent) or Rs.5000.00 whichever is higher of the awarded amount within the **7 days** after award of work. This guarantee shall be in the form of Banker's cheque/ Demand Draft/ Pay order/ Bank Guarantee/ FDR of any Scheduled Bank or the State Bank of India in accordance with the prescribed form. In case the contractor fails to deposit the said performance guarantee within **7 days** after award of work, the Earnest Money deposited by the contractor shall be forfeited automatically without any notice to the contractor. The earnest money deposited along with bid shall be returned after receiving the aforesaid performance guarantee. **The performance guarantee shall be kept till satisfactory handing over of site to NHSRC.**

Name of the work: Providing and Fixing pre-coated galvanised iron Sheet with MS Frame at PSS and BSES Metering panel at NHSRC, NIHFW Campus, Munirka, New Delhi-110067.

Schedule of Quantity

Item no	Description	Unit	Qty	Rates		Amount
				In Words	In figures	
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil.	Cum	0.45			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).	Cum	0.45			
3	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc.complete. Hot finished welded type tubes	Kg	702.88			

4	Providing and fixing pre-coated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length up to 12 metre or as desired by Engineer in- charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete up to any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	Sqm	42.78			
---	--	-----	-------	--	--	--

TOTAL

Rupees-----only-

(Rate should be quoted in words and in figure both)

Signature of Vendor/Contractor with Seal of Company

Address:-