

# NATIONAL HEALTH SYSTEM RESOURCE CENTER



## DETAIL SUMMARY OF SEALED QUOTATION

Name of Work	Misc civil works for Provision of ramp for physical disabled person access at NHSRC office (Display Hall) at NIHFV campus, Munirka New Delhi-110067.
Date of issue of Quotation	28.12.2015
Date of issue of Quotation documents.	From 28.12.2015 to 05.01.2016, can be downloaded from the website of NHSRC, New Delhi
Date of submission of Quotation	The sealed quotation so as to reach this office on or before 05.01.2016 latest by 1400 hrs
Date of opening of Quotation	On 05.01.2016 at 1430 hrs in presence of party who may be present.
Estimate cost	Rs.47,852.29
Completion time	15 Days

  
Dr. Uddipan Dutta  
Principal Administrative Officer  
NHSRC

# NATIONAL HEALTH SYSTEM RESOURCE CENTER



## QUOTATION

**Ref: - NHSRC/Admin/Infra/2**

**Date:-28/12/2015**

**Name of the work: Misc civil works for Provision of ramp for physical disabled person access at NHSRC office (Display Hall) at NIHFV campus, Munirka New Delhi-110067.**

1. Sealed item rate quotations are invited for above said work.
2. The work to be completed within 15 Days from the date of written instructions to carry out work.
3. The rates quoted by the contractor are inclusive of labour, T&P, wastage of labour if any, working in odd hours, all taxes etc.
4. Necessary deductions shall be made on account of statutory deductions as applicable.
5. The work shall be done as per CPWD Specifications.
6. The sealed quotation so as to reach this office on or before 5.1. 2016 latest by 1400 hrs. The quotation will be opened at 1430 Hours on the same day.
7. Estimate Prepared on the basis of CPWD DSR 2014 and Market Rate.
8. The payment will be made after satisfactory completion of work and on actual measurement.

### Schedule of Quantity

S.no	Description	Unit	Qty	Rate in figures	Rate in words	Amount
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size	Cum	0.777			
2	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick	Sqm	10.30			

3	Providing and fixing stainless steel ( Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	Kg	48.96			
4	Reducing the size of Iron grill gate i.e.2.5Inches from floor level by cutting the Iron Grill middle section and fixing of existing floor angle with modified portion and fixing the same in position with welding and painting the complete door from both sides complete in all respect as per the direction of Engineer In Charge.	LS	1			
		TOTAL				Rs.

Rupees-----only-

(Rate should be quoted in words and in figure both)

Signature of Vendor/Contractor with Seal of Company

Address:-