

QUOTATION

A.01/04/08-PF-2

6.11.2015


Sealed item rates quotations are hereby invited from reputed vendors/contractors for Preparing and fixing of storage almirahs, shifting of Partition wall and renovation of pantry room at NHSRC..The quotations so as to reach this office on or before 12.11.2015 latest by 2.00 P.M. The quotations will be opened on same day at 2.30 P.M. The discription of items are given below.

Sl. No.	Description of Items	Qty	Rate	Unit	Total Amount
1	Providing and fixing of Storage arlimrahs in between space of gents and ladies toilets of Size: 8' 00 (H)x 3'-6" (W) x 2'-00" depth approx) with made of 19 mm waterprrofiging ply and all side laminate finishing in all respect.	28		Sqft	
2	Shifting of partition wall and doors of A-8 to corner side of wall towards threatre room and making good the same.	120		Sqft	
3	Providing and fixing of Storage arlimrahs in pantry room of Size: 8' 00 (H)x 3' (W) x 2'-00" depth approx) with made of 19 mm waterprrofiging ply and all side laminate finishing in all respect.	12		Sqft	
4	Providing and fixing of folding table of 11' in lenth with made of 19 mm waterprrofiging ply and all side laminate finishing in all respect.	1 Job		L.S.	
5	Making space in existing over head storage by cutting in the storage almirah to keep the Microwave in the existing almirahs	1 job		L.S.	
6	Providing and fixing overhead storage almirahs above the sink to keep the cup and plate in the almirahs.	12		Sqft	

7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: 6.1.1 Cement mortar 1:4 (1 cement : 4 coarse sand)	12	Sqft
8	15 mm cement plaster on rough side of single or half brick wall finished with a floating coat of neat cement of mix : 1:3 (1cement: 3 coarse sand)	5	Sqft
9	Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately).		
	Size of Tile 500x500 mm	5	Sq mtr
		Total	

Terms and conditions:-

1. The work to be completed in 7 days of issue of work order.
2. Payment against completion of Work.
3. Payment shall be made on actual measurement of work.


 Dr. Uddipan Dutta
 Principal Administrative officer
 NHSRC

Signature of Contractor/Vendors
Address